

Technical & Commercial Offer — Final

Lighthief Cyprus Ltd — Exclusive Linyang Energy Distributor & EPC Partner

28 October Ave 249, Lophitis Business Center 1, Office 201, 3035 Limassol, Cyprus

Client: Confidential — Western Greece PV operator (via partner enquiry)

Project: 15 MW / 30 MWh BESS — behind-the-meter add-on to existing PV plant, Western Greece

Application: BTM storage co-located with operating photovoltaic installation

Ref: LCY-IND-GREECE-2026-05 **Date:** 15 May 2026 **Valid:** 30 days

€4,777,759

TURNKEY PRICE (EX VAT)

15 MW

RATED POWER

30.09 MWh

STORAGE CAPACITY

2.0 h

DURATION

Model	Description	Photo	Qty
Linyang Power Atlantic 5.015 MWh	Containerised battery storage Cell: EVE 314Ah LFP Voltage: 1164.8–1497.6 Vdc Cooling: Liquid cooling (45 kW) Protection: IP55 / C5 corrosion BMS: 3-level (96 BMU modules) Fire suppression: Integrated Comms: Modbus TCP, IEC 104/61850 Container: 20ft High Cube		6
Kehua BCS1250K-C-HUD (T4 MV Skid)	40ft HC containerised MV skid (T4) 4 × PCS BCS1250K (1.25 MW each) = 5.0 MW per skid Transformer: SL-5000 (5,000 kVA) Ratio: 0.69/22 kV (or as per site MV), Dy11, oil-immersed Each PCS: 1500 Vdc, 690 Vac, IP65, ≥99% eff. Grid-forming: VSG, Black-Start Grid code: EN 50549-2 (TÜV) 3 skids in parallel = 15 MW total		3
Voltus EMS / SCADA	Energy Management System (EMS/SCADA) PV + BESS co-optimisation for behind-the-meter operation Grid interface and export/import control Market-scheduled charge/discharge profiles Remote monitoring, alarms, and reporting Customer training and O&M handover support		1

Turnkey EPC Price (ex VAT): **€4,777,759**

Configuration — 3 × 5 MW / 10 MWh parallel strings: Each string comprises 2 × Linyang Power Atlantic 5.015 MWh battery containers plus 1 × T4 MV skid (4 × BCS1250K = 5.0 MW). DC cabling connects each battery container to its dedicated PCS pair (2 × 1.25 MW per container). Three strings operate in parallel for **15 MW / 30.09 MWh** total. Layout allows phased energisation of individual strings where permitted by the site MV arrangement.

Specification compliance: 15 MW / 30 MWh as requested. 2.0 h duration class (MW × 2). 7,000 warranted cycles at 1 cycle/day. Grid code: EN 50549-2 TÜV certified PCS.

Behind-the-meter integration: EMS coordinates BESS with the existing PV plant — charging from surplus PV, peak shaving, and export management within the site connection limits. Interface to existing site SCADA/inverter infrastructure to be confirmed at detailed design stage.

Greece delivery: EPC delivered via Lighthief Cyprus with local Greece engineering support (TEE-licensed partner). Grid connection coordination with HEDNO/ADMIE as applicable. CIF arrival port in Greece to be confirmed (Piraeus or Thessaloniki subject to logistics).

Lighthief Cyprus Ltd (HE 477423) — office@lighthief.com — +357 99 164 158

This offer is confidential. All prices exclude VAT (24%) and battery recycling fees. Subject to final Linyang equipment confirmation within 5 working days of acceptance.

Scope of Works, Warranty & Payment Terms

✓ Included in Turnkey Price

- 6 × Battery Containers (5.015 MWh)
- 3 × T4 MV Skid (4 × BCS1250K PCS + SL-5000 transformer each)
- Voltus EMS — PV + BESS co-optimisation and remote monitoring
- DC, MV, LV and communications cabling and containment (within BESS compound)
- Internal SPDs + earthing integration within BESS scope
- Electrical & mechanical design drawings for installation
- Project engineering & management
- Load flow, short-circuit, earthing, and selectivity studies (BESS scope)
- Freight + all-risks insurance (marine + port to site)
- Customs clearance + import duties (Greece)
- Delivery, unloading, positioning at site
- Civil works — foundations and trenching within BESS compound only
- Installation, connection, and termination
- Programming, configuration, pre-commissioning
- Testing and commissioning with HEDNO/ADMIE coordination
- Protection relay settings + onsite testing
- Customer training and handover documentation
- As-built drawings and manuals (electronic format)
- Health & Safety Plan as required by legislation
- Construction insurance (CAR/EAR, TPL) as required
- 5-year base warranty on BESS and PCS/MVS equipment

✗ Exclusions

- VAT (24% — Greece)
- Licensed connection / permit drawings (TEE-stamped) — client or local consultant
- External lightning protection system (LPS) beyond container OEM scope
- General earthworks, levelling, and road works outside BESS compound
- Soil investigation, topographic surveys, geotechnical studies
- PCC / MV substation extension or new bay supply (if required)
- HEDNO/ADMIE witness fees beyond standard commissioning attendance
- Telecoms OPEX (SIM/data plans for remote access)
- Security systems (CCTV, alarms, fire detection beyond OEM)
- Perimeter fencing + site lighting
- Battery recycling / end-of-life fees

Year-10 Capacity

30.09 MWh × 80% = **24.07 MWh** usable at Year 10.
SOH: ≥85% (Yr5), ≥79.58% (Yr10), ≥70% (Yr15).

Extended Warranty (Yr 6–10)

Paid directly to Linyang — not in EPC price:

BESS: €913.92/MWh/yr = €27,418/yr

PCS+MVS: €747.76/MWh/yr = €22,433/yr

Combined: €49,851/yr for 30 MWh

Warranty & LTSA

Period	BESS Warranty	PCS+MVS	Combined/MWh/yr	LTSA O&M
Years 1–5	Included in EPC		€0	€1,740/MWh/yr
Years 6–10	€913.92	€747.76	€1,661.68	€1,740/MWh/yr
Years 11–15	€1,157.62	€926.10	€2,083.72	€1,740/MWh/yr

Extended warranty (Years 6+) paid directly to Linyang Energy. LTSA: 24/7 monitoring, 97% availability, 4hr remote / 8hr on-site response. Annual LTSA (30 MWh) = €52,200/yr.

Payment Terms

Milestone	%	Amount	Trigger
Advance Payment	25%	€1,194,440	Within 7 days of contract signing
Ready to Ship	50%	€2,388,880	Factory inspection passed
On-Site Delivery	20%	€955,552	Equipment arrives at site
Commissioning (SAT)	5%	€238,887	System commissioned & tested

Total: €4,777,759 (100%)

Delivery Timeline

Phase	Duration
Design & engineering	2–3 weeks (concurrent with production)
Production	~13 weeks (90 days)
Sea transport (Shanghai → Greece — port TBC)	~7 weeks (50 days)
Customs + inland transport	1–2 weeks
Installation & commissioning	4–6 weeks

Total: ~26–30 weeks from contract signing

Site note: Final cable routes, MV point of connection, and PV integration interface to be confirmed at site visit. Timeline assumes unobstructed site access and timely grid-operator coordination.

Valid 30 days. Civil works assumes standard ground conditions. Price subject to final Linyang standalone equipment confirmation.

Equipment Overview

Component	Photo	Component	Photo
Battery Container Linyang Power Atlantic 5.015 MWh 20ft HC		Cell Racks (Interior) 96 BMU modules Liquid cooling Fire suppression	
T4 MV Skid 4 × BCS1250K = 5.0 MW 40ft HC SL-5000 transformer		Parallel String Layout 3 × (2 BESS + T4 skid) 5 MW / 10 MWh per string	
PCS — BCS1250K 1.25 MW IP65 EN 50549-2 Certified		EVE LFP Cell Pack 314Ah 3.2V nominal UL 9540A certified	

Attached Technical Datasheets

#	Document	Description
A1	5MWhSpecification.pdf	Battery container full specification
A2	Degradation Curve_5MWh.pdf	Battery degradation curves
A3	BCS1250K-C-HUD Series.pdf	PCS datasheet (BCS1250K model)
A4	BCS4000K-C-HUD T4.pdf	T4 MV Skid datasheet (4 × 1.25 MW = 5.0 MW)
A5	3 × 5 MW String Layout.pdf	Parallel string architecture — 3 × (2 BESS + T4 skid)
A6	MV Transformer 5000kVA Datasheet.pdf	SL-5000 transformer (T4 skid)
A7	BTM PV Integration Note.pdf	EMS integration with existing PV plant (to be finalised at site visit)
A8	BCS1250K-C-HUD EN50549-2 Report.pdf	EN 50549-2 grid code TÜV certification
A9	Linyang Warranty Terms v2.pdf	OEM warranty terms and conditions

Next Steps

1. **Offer acceptance**
2. **Site visit** — BESS layout, MV connection point, PV integration, cable routing, Greece grid requirements
3. **Contract signing + advance payment** — triggers 90-day production
4. **Factory Acceptance Test** — client invited
5. **System operational** — ~26–30 weeks from contract signing

Lighthief Cyprus Ltd (HE 477423) | 28 October Ave 249, Lophitis Business Center 1, Office 201, 3035 Limassol
Alexander Papacosta — Cyprus Director — office@lighthief.com — +357 99 164 158 | www.solarfarms.cy

Disclaimers: Valid 30 days. Price subject to final Linyang standalone confirmation (within 5 working days). Excludes VAT (24%) and battery recycling fees. Year-10 SOH 80% subject to Linyang confirmation (standard 79.58%). Extended warranty paid to Linyang directly. Army firing range access may affect timeline.