



Crane & Heavy Transport Services — BESS Container Delivery

All 2026 Batches — 46 Parks · 251 Containers · 5 Districts · Limassol Port to Site
Equipment: Linyang Energy LFP Battery Energy Storage Systems

TO: A. SOULIS — Special Lifting & Heavy Haulage

Attention: Stephanos Soulis, General Manager
Tel: +357 24642430 | **Mobile:** +357 99522736
Email: stephanos@souliscranes.com | asoulis@spidernet.com.cy
Web: www.soulis-cranes.com.cy

DOCUMENT REFERENCE	
From	Costas — Lighthief Cyprus Ltd (costas@lighthief.com)
Company	Lighthief Cyprus Ltd, 28 October Ave 249, Lophitis Business Center 1, Office 201, 3035 Limassol
Previous RFQ	RFQ-LCY-TRANS-2026-001 (27 January 2026) — fleet confirmation received 22 Feb 2026
This Document	LCY-RFP-CRANE-2026-001 — Updated RFP with confirmed batch schedule, container quantities, and delivery timeline
Proposal Deadline	12 March 2026
Project Start	First delivery: 12 July 2026 (Batch 1 port clearance)
Project End	Last delivery: ~18 October 2026 (Batch 3 final site delivery)

Contents

- 1. Project Overview
- 2. Container Specifications — Types, Sizes & Weights
- 3. 2026 Batch Schedule & Port ETA
- 4. Delivery Matrix — By Batch, District & Destination

5. Scope of Work
6. Pricing Template
7. Fleet & Capacity Requirements
8. Terms & Conditions
9. Required Information from Vendor

1. Project Overview

Lighthief Cyprus Ltd is the exclusive distributor and EPC contractor for a portfolio of 46 Battery Energy Storage System (BESS) parks being delivered across Cyprus in 2026. All equipment ships CIF Limassol from Linyang Energy (Shanghai, China) and requires crane unloading and heavy haulage transport from Limassol Port to solar park sites across 5 Cyprus districts.

PARAMETER	VALUE
Total Parks (2026 delivery)	46
Total Installed Capacity	221.5 MW / 793 MWh
Total Containers	251
Delivery Batches	3 (July – October 2026)
Port of Arrival	Limassol Port (ECTL terminal)
Incoterms	CIF Limassol
Delivery Districts	Nicosia, Famagusta, Larnaca, Limassol, Paphos
Equipment Manufacturer	Linyang Energy (LFP battery containers & PCS/MV skids)
Estimated Total Weight	~10,200 tonnes (all containers)

Previous Engagement: A. Soulis provided a reference quotation (November 2025) for Limassol Port → Ayios Kendeas: 6× 20HC (43t) + 4× 20' Standard (15t), transport + crane unload = €23,600 (~€2,360/container). Fleet confirmation received 22 February 2026: 6× 20ft trucks (43T capacity) confirmed. Current transport budget: €604,160 (251 containers × €2,360). This RFP seeks formal pricing for the full 2026 programme across all routes and batches.

2. Container Specifications — Types, Sizes & Weights

There are two container types across the portfolio. Both require crane placement on prepared reinforced concrete foundations at each site.

TYPE A — Battery Container (BESS)

ISO Type:

20' High Cube (20HC)

External Dimensions:

6,058 mm × 2,438 mm × 2,896 mm

Height:

2,896 mm (9 ft 6 in)

Weight (loaded):

~41.5 – 43 tonnes

Contents:

LFP Battery Cells (EVE 314Ah) + BMS + HVAC

Cooling + Fire Suppression

Capacity:

5.015 MWh per container

Crane Requirement:

Minimum 50-tonne mobile crane

IMO Class:

Class 9 (Lithium batteries)

TYPE B — MV SKID / PCS Container

ISO Type:

40' High Cube (40HC) or 20' High Cube (20HC)*

External Dimensions (40HC):

12,192 mm × 2,438 mm × 2,896 mm

External Dimensions (20HC):

6,058 mm × 2,438 mm × 2,896 mm

Weight (loaded):

~35 – 38 tonnes (40HC) / ~28 – 32 tonnes (20HC)

Contents:

PCS Inverter (Kehua) + MV Transformer + MV Switchgear

Crane Requirement:

Min 50T (20HC) / Min 80T (40HC)

Note:

*Smaller parks (≤ 2.5 MW) use 20HC skids; larger parks use 40HC

2.1 Weight Summary by Container Type

CONTAINER TYPE	ISO SIZE	DIMENSIONS (L × W × H)	UNIT WEIGHT (LOADED)	MIN. CRANE CAPACITY
BESS Battery Container	20' High Cube	6,058 × 2,438 × 2,896 mm	41.5 – 43 tonnes	50 tonnes
MV SKID (large parks ≥ 5 MW)	40' High Cube	12,192 × 2,438 × 2,896 mm	35 – 38 tonnes	80 tonnes
MV SKID (small parks ≤ 2.5 MW)	20' High Cube	6,058 × 2,438 × 2,896 mm	28 – 32 tonnes	50 tonnes

Heavy Load Warning: All BESS containers weigh approximately 43 tonnes — exceeding standard road freight limits. Heavy load permits, police escorts, and appropriate low-loader trailers are mandatory. All containers contain lithium batteries (IMO Class 9) — no special ADR requirements for road transport within Cyprus, but driver awareness of contents is required.

2.2 Lifting Requirements

REQUIREMENT	SPECIFICATION
Lifting Points	ISO corner castings (top + bottom); certified for crane lift
Spreader Bar	Required for 40HC containers to prevent bowing
Placement Tolerance	±50 mm of marked foundation positions
Levelling	Containers must be level on foundation (shimming may be required)
Foundation Type	Reinforced concrete pad (prepared in advance by Lighthief subcontractors)
Container Spacing	6 m minimum between containers (FM 5-33 / NFPA 855 compliant)
Site Access	6 m wide access road at each site; crane must operate from hardstanding

3. 2026 Batch Schedule & Port ETA

All containers arrive at **Limassol Port (ECTL terminal)** in three batches. Port clearance typically takes 5–7 working days. Transport from port to sites should commence immediately after clearance to minimise port storage charges (4 days free storage, then €8/container/day escalating).

BATCH	DESCRIPTION	PARKS	CONTAINERS	ETA LIMASSOL PORT	PORT CLEARANCE COMPLETE	TRANSPORT WINDOW	DESTINATION DISTRICTS
Batch 1	ABIO Phase 1	15	80	5 July 2026	~12 July 2026	12 Jul – 5 Aug 2026	Nicosia only
Batch 2	ABIO Phase 2 + Timotheos	19	90	20 August 2026	~27 August 2026	27 Aug – 15 Sep 2026	Nicosia, Larnaca, Paphos
Batch 3	Esperia Phase 1 + Standalone	12	81	20 September 2026	~27 September 2026	27 Sep – 18 Oct 2026	Famagusta, Limassol, Paphos, Nicosia
TOTAL — ALL 2026 BATCHES		46	251	July – September 2026		Jul – Oct 2026	5 districts

Scheduling Note: Batch ETAs are based on 50-day shipping from Shanghai. Actual arrival may vary ±7 days. Lighthief will provide 14 days advance notice of confirmed vessel arrival for each batch. Crane and transport must be available within 48 hours of port clearance completion.

3.1 Estimated Total Weight by Batch

BATCH	CONTAINERS	MWH	ESTIMATED BESS (20HC, ~43T)	ESTIMATED MV SKID (MIXED, ~35T)	EST. TOTAL WEIGHT
Batch 1	80	280	~56 containers × 43t	~24 containers × 35t	~3,248 tonnes
Batch 2	90	230	~46 containers × 43t	~44 containers × 35t	~3,518 tonnes
Batch 3	81	283	~57 containers × 43t	~24 containers × 35t	~3,291 tonnes
TOTAL	251	793	~159 containers	~92 containers	~10,057 tonnes

4. Delivery Matrix — By Batch, District & Destination

All deliveries originate from **Limassol Port (ECTL terminal)**. Containers are transported to solar park sites across 5 Cyprus districts. The following tables detail the number of containers per batch, per district, with estimated transport distances.

4.1 Batch 1 — ABIO Phase 1 (ETA Port: 5 July 2026 | Transport: 12 Jul – 5 Aug 2026)

DISTRICT	PARKS	MWH	CONTAINERS	EST. DISTANCE FROM PORT	NOTES
NICOSIA DISTRICT					
Nicosia region	15	280	80	~85–95 km	Entire batch in single district — efficient crane routing. Villages include Potamia, Agios Sozomenos, Tseri, Dali area
Batch 1 Total			80	Single route: Limassol → Nicosia (~90 km)	

4.2 Batch 2 — ABIO Phase 2 + Timotheos (ETA Port: 20 Aug 2026 | Transport: 27 Aug – 15 Sep 2026)

DISTRICT	PARKS	MWH	CONTAINERS	EST. DISTANCE FROM PORT	NOTES
NICOSIA DISTRICT					
Nicosia region	14	160	65	~85–95 km	ABIO Ph.2 (5 parks) + Timotheos (9 parks)
LARNACA DISTRICT					
Larnaca region	4	48	17	~65–75 km	ABIO cluster — Greendorado area
PAPHOS DISTRICT					
Polemi / Paphos	1	22	8	~60–70 km	Single ABIO park (Polemi)
Batch 2 Total			90	3 routes: Nicosia, Larnaca, Paphos	

4.3 Batch 3 — Esperia Phase 1 + Standalone Groups (ETA Port: 20 Sep 2026 | Transport: 27 Sep – 18 Oct 2026)

DISTRICT	PARKS	MWH	CONTAINERS	EST. DISTANCE FROM PORT	NOTES
FAMAGUSTA DISTRICT					
Famagusta / Frenaros area	5	180	52	~120–135 km	Esperia cluster (3 parks) + Galascope (2 parks) — largest district concentration. Includes 1 park with 14+ containers (largest single site)
LIMASSOL DISTRICT					
Limassol / Ayios Kendeas	3	40	14	~30–50 km	Esperia (1 park) + Andreadis (2 parks). Shortest transport route
PAPHOS DISTRICT					
Paphos region	3	20	7	~60–70 km	Kerasi group (3 parks)
NICOSIA DISTRICT					
Nicosia region	1	25	8	~85–95 km	Karis standalone (single large park)
Batch 3 Total			81	4 routes: Famagusta, Limassol, Paphos, Nicosia	

4.4 District Summary — All Batches Combined

DISTRICT	TOTAL PARKS	TOTAL CONTAINERS	BATCHES PRESENT	DISTANCE FROM LIMASSOL PORT	% OF CONTAINERS
Nicosia	30	153	Batch 1, 2, 3	~85–95 km	61.0%
Famagusta	5	52	Batch 3	~120–135 km	20.7%
Larnaca	4	17	Batch 2	~65–75 km	6.8%
Limassol	3	14	Batch 3	~30–50 km	5.6%
Paphos	4	15	Batch 2, 3	~60–70 km	6.0%
TOTAL	46	251	3 batches	30–135 km range	100%

Key Routing Insight: 61% of all containers (153 of 251) go to Nicosia district. Optimising the Limassol → Nicosia route is critical to overall cost and throughput. The Famagusta route is longest (~130 km) but carries the second-largest volume (52 containers). Limassol local deliveries (14 containers, ~30–50 km) are the shortest and most efficient.

5. Scope of Work

5.1 Services Required

SERVICE	DESCRIPTION	RESPONSIBILITY
Port Collection	Collect containers from Limassol Port (ECTL) container yard after customs clearance	A. Soulis
Heavy Haulage Transport	Transport containers on low-loader trailers from Limassol Port to destination park sites across all 5 Cyprus districts	A. Soulis
Heavy Load Permits	Arrange all necessary heavy load transport permits from Cyprus authorities	A. Soulis
Police Escorts	Arrange police escorts where required by law for oversized/overweight loads	A. Soulis
Mobile Crane Provision	Supply mobile crane(s) at each destination site for container unloading	A. Soulis
Crane Unloading	Lift containers from trailer and place onto prepared reinforced concrete foundations	A. Soulis
Precision Positioning	Final alignment of containers per site layout drawings (±50 mm tolerance)	A. Soulis TO BE DISCUSS ADDITIONAL COST
Levelling	Ensure containers are level on foundation; shimming if required	A. Soulis TO BE DISCUSS ADDITIONAL COST

5.2 Lighthief Responsibilities (Not in Scope for A. Soulis)

ITEM	DETAIL
Customs clearance & port landing charges	Handled by Interfreight (separate contract)
Concrete foundation preparation	Completed before container arrival by Lighthief subcontractors
Site layout drawings & marking	Provided by Lighthief prior to delivery day
Site access & hardstanding for crane	Confirmed suitable by Lighthief before scheduling delivery
On-site coordination / supervision	Lighthief site supervisor present during all crane operations

5.3 Crane Specifications Required

REQUIREMENT	20HC CONTAINERS (BESS + SMALL MV)	40HC CONTAINERS (LARGE MV SKID)
Minimum Crane Capacity	50 tonnes	80 tonnes
Maximum Lift Weight	43 tonnes	38 tonnes
Lift Height	~4 m (onto foundation + clearance)	~4 m (onto foundation + clearance)
Working Radius	~8–12 m typical	~10–15 m typical
Spreader Bar	Optional (ISO corner castings)	Required (to prevent bowing)
Ground Bearing Pressure	Outrigger mats required on unprepared ground	Outrigger mats required on unprepared ground

6. Pricing Template

Please complete the pricing tables below. Pricing should be all-inclusive (transport + crane unloading + positioning + permits + escorts). Alternatively, provide separate rates for transport and crane if preferred.

6.1 Unit Rates — By Route & Container Type

ROUTE (LIMASSOL PORT →)	DISTANCE	20HC BESS (~43T) € PER CONTAINER	40HC MV SKID (~38T) € PER CONTAINER	20HC MV SKID (~30T) € PER CONTAINER
Limassol district sites	30–50 km	2,500.00	2,500.00	2,500.00
Paphos district sites	60–70 km	2,500.00	2,500.00	2,500.00
Larnaca district sites	65–75 km	2,500.00	2,500.00	2,500.00
Nicosia district sites	85–95 km	2,500.00	2,500.00	2,500.00
Famagusta district sites	120–135 km	2,500.00	2,500.00	2,500.00

6.2 Batch Totals — Estimated Cost

BATCH	CONTAINERS	PRIMARY DISTRICT(S)	ESTIMATED TOTAL COST (€)
Batch 1 (Jul 2026)	80	Nicosia (100%)	2,500.00
Batch 2 (Aug 2026)	90	Nicosia (72%) / Larnaca (19%) / Paphos (9%)	2,500.00
Batch 3 (Sep 2026)	81	Famagusta (64%) / Limassol (17%) / Paphos (9%) / Nicosia (10%)	2,500.00
TOTAL	251	All 5 districts	627,500.00

6.3 District Totals

DISTRICT	TOTAL CONTAINERS	COST PER CONTAINER (€)	DISTRICT TOTAL (€)
Nicosia	153	2,500.00	382,500.00
Famagusta	52	2,500.00	130,000.00
Limassol	14	2,500.00	35,000.00
Larnaca	17	2,500.00	42,500.00
Paphos	15	2,500.00	37,500.00
TOTAL	251		627,500.00

6.4 Volume Discount & Framework Agreement

TIER	DESCRIPTION	DISCOUNT OFFERED (%)
Full 2026 Programme	251 containers over 4 months (Jul–Oct 2026)	N/A
Framework Agreement	12-month standing rate for all deliveries	N/A
Batch Commitment	Per-batch confirmed booking (min 80 containers)	N/A

6.5 Additional Charges (if applicable)

ITEM	RATE (€)	NOTES
Weekend / public holiday delivery	50%	Premium rate if applicable
Night transport (22:00–06:00)	N/A	If permitted / required for heavy loads
Waiting time (beyond 2 hours at site)	500.00	Per hour
Additional crane mobilisation/demobilisation	3,000.00	If crane must travel to remote site separately
Fuel surcharge mechanism		If applicable — base fuel price reference

7. Fleet & Capacity Requirements

7.1 Throughput Targets

BATCH	CONTAINERS	TRANSPORT WINDOW	WORKING DAYS	REQUIRED THROUGHPUT
Batch 1	80	12 Jul – 5 Aug 2026	~18	~5 containers/day
Batch 2	90	27 Aug – 15 Sep 2026	~14	~7 containers/day
Batch 3	81	27 Sep – 18 Oct 2026	~15	~6 containers/day

Based on your confirmed fleet (22 Feb 2026): 6× 20ft trucks at 43T capacity can deliver ~12 containers/day (assuming 2 round trips per truck for Nicosia route). Batch 2 requires the highest daily throughput (~7/day across 3 districts). 40HC truck availability needs confirmation for MV SKID containers.

7.2 Fleet Confirmation Required

ITEM	CONFIRMED (22 FEB)	REQUIRED FOR FULL PROGRAMME	STATUS
20ft low-loader trucks (43T capacity)	6 trucks	6 trucks minimum	CONFIRMED
40ft low-loader trucks (38T capacity)	TBC	2–3 trucks	REQUIRED
Mobile crane — 50T class	TBC	1 minimum (2 preferred for parallel operations)	REQUIRED
Mobile crane — 80T class	TBC	1 minimum (for 40HC containers)	REQUIRED
Crane operators (certified)	TBC	2 minimum	REQUIRED
Transport drivers (heavy licence)	TBC	6 minimum	REQUIRED

7.3 Peak Demand Periods

PERIOD	ACTIVE BATCHES	CONTAINERS IN TRANSIT	CRANE DAYS REQUIRED
12–31 July 2026	Batch 1	80	~14 days
27 Aug – 15 Sep 2026	Batch 2	90	~14 days
27 Sep – 18 Oct 2026	Batch 3 (widest geographic spread)	81	~15 days (incl. crane travel between districts)

8. Terms & Conditions

ITEM	REQUIREMENT
Price Validity	Pricing to remain valid for 12 months from contract signature
Call-Off Orders	5 working days notice for individual deliveries within each batch
Advance Batch Notice	Lighthief provides 14 days notice of batch arrival at port
Insurance — Goods in Transit	Full goods-in-transit coverage required (min €500,000 per load) Our company has coverage €440,000.00. If required coverage €500,000.00 an extra cost of €1,500.00 will be apply.
Insurance — Public Liability	Min €2,000,000 public liability coverage Our company has coverage €5,0000,000.00
Insurance — Crane Operations	Crane and rigging liability coverage for full lift value As per our public liability coverage
Waiting Time	First 2 hours on-site included; thereafter hourly rate applies
Payment Terms	30 days from delivery confirmation (per batch invoice) TO BE DISCUSS
Cancellation	Batch cancellation with 14 days notice at no charge; <14 days: mobilisation costs only TO BE DISCUSS
Force Majeure	Standard force majeure clause — neither party liable for delays beyond reasonable control
Health & Safety	Full compliance with Cyprus H&S regulations; risk assessment required for each site
Heavy Load Permits	All permits to be arranged and paid for by contractor (included in quoted rates)

9. Required Information from Vendor

Please provide the following with your proposal by **12 March 2026**:

#	ITEM	DETAIL
1	Completed pricing tables	Sections 6.1 through 6.5
2	Fleet confirmation	Number and type of trucks (20ft and 40ft low-loaders), crane models and capacities Six Heavy Duty Tractors Units & six low bed trailers. LIEBHERR LTM1095 LIEBHERR LTM1100 DEMAG AC100 DEMAG AC160 LIEBHERR LTM1200 DEAMG AC250
3	Lead time per delivery	Estimated hours from port collection to site placement, per route
4	Daily throughput capacity	Maximum containers per day per route (with current fleet) Max. six pieces per day but it depends also from other factors as weather conditions, police escort availability etc
5	Crane availability schedule	Confirm crane availability for Jul–Oct 2026 window; any prior commitments Confirm
6	Insurance certificates	Goods-in-transit (min €500K/load), public liability (min €2M), crane operations coverage
7	Heavy haulage licence	Current heavy haulage licence confirmation (Cyprus)
8	Reference projects	3+ reference projects involving heavy container/equipment transport (similar weights: 35–43 tonnes) COL GROUP: scope of works 2024 – 2025 20pcs Transport and unloading of Transformers 10MVA & 20MVA loaded on flat rack for EAC sub-stations and warehouses 2026 – 2027 19pcs Transport and unloading of Transformers 40MVA loaded on flat rack for EAC sub-stations and warehouses APR ENERGY: scope of works Transport and unloading of 160pcs containerized generators at Moni station VESTAS MED CYPRUS LTD: scope of works at Kelia Wind Farm Port handling, transport and erection of 75pcs Wind Generator components consisting of up to 82meters long special transport

9	Safety record	H&S record for past 3 years; any incidents involving crane operations or heavy haulage
10	Subcontracting	Confirm if any element will be subcontracted; if so, identify subcontractor(s)

Lighthief Contact for This RFP

Costas

Email: costas@lighthief.com

Company: Lighthief Cyprus Ltd

Address: 28 October Ave 249, Lophitis Business Center 1, Office 201, 3035 Limassol, Cyprus

Tel: +357 77 77 00 50

Reference: LCY-RFP-CRANE-2026-001

Proposal Deadline: 12 March 2026

Confidentiality: This RFP and all information contained herein is confidential and intended solely for A. Soulis Special Lifting & Heavy Haulage. It may not be shared with third parties without written consent from Lighthief Cyprus Ltd.

Lighthief Cyprus Ltd · 28 October Ave 249, Lophitis Business Center 1, Office 201, 3035 Limassol, Cyprus
Costas · costas@lighthief.com · +357 77 77 00 50

Document: LCY-RFP-CRANE-2026-001 · Classification: COMMERCIAL — CONFIDENTIAL
Supersedes: RFQ-LCY-TRANS-2026-001 (27 January 2026)
Date: 26 February 2026