


THIS DIAGRAM IS PRELIMINARY AND INDICATIVE ONLY



GENERAL NOTES:

- THIS IS A HIGH LEVEL CONCEPTUAL DIAGRAM ONLY. ACTUAL ELECTRICAL DESIGN WILL BE DETERMINED DURING THE DESIGN PHASE AND MIGHT DEVIATE SIGNIFICANTLY FROM THIS CONCEPTUAL DIAGRAM.
- THE POINT OF CONNECTION IS ASSUMED TO BE AT MEDIUM VOLTAGE. FOR A POINT OF CONNECTION AT HIGH VOLTAGE ADDITIONAL EQUIPMENT IS REQUIRED.
- DUAL SECONDARY TRANSFORMERS MIGHT BE REQUIRED TO LIMIT SHORT CIRCUIT CURRENTS ON THE LOW VOLTAGE SIDE
- SPD REQUIREMENTS ON LOW AND MEDIUM VOLTAGE MUST BE DETERMINED FOLLOWING IEC-62305 OR EQUIVALENT APPLICABLE STANDARD
- BATTERY METER MUST BE SEL-735 AS PER TESLA REQUIREMENTS FROM THE SITE DESIGN MANUAL AVAILABLE IN THE TESLA PARTNER PORTAL
- THE CIRCUIT BREAKERS AT THE LOW VOLTAGE SIDE OF THE TRANSFORMERS ARE OPTIONAL. WHEN INSTALLED, THEY SHOULD BE ACCESSIBLE TO TESLA AND PROVIDED WITH LOTO FACILITY. FOR EQUIPMENT SUPPLY ONLY PROJECTS, WHEN ACCESIBLE LV BREAKERS ARE NOT PROVIDED CUSTOMER MUST PERFORM MV SWITCHING AT TESLA CONVENIENCE



TESLA MOTORS, INC.
3500 DEER CREEK RD.
PALO ALTO, CA 94304
(650) 681-5000

PRELIMINARY
NOT FOR
CONSTRUCTION

MV SINGLE LINE
DIAGRAM
TESLA ENERGY

NO.	REVISION	DATE	INT.	DX						
1	INDICATIVE SINGLE LINE DIAGRAM	05/09/2022								

ORIGINAL SIZE:
297x420mm
SHEET SIZE ISO A3

SHEET TITLE
INDICATIVE LAYOUT

SHEET NUMBER

PROPRIETARY AND CONFIDENTIAL