

Offer 3 of 3 — 132/33 kV Substation & TS Connection (EPC)

Power On BESS — 59 MW / 120 MWh, Plot 26, Psevdas, Larnaca, Cyprus

Client: H.E.S.S. Hybrid Energy Storage Systems Ltd

Offer ref: LTH-FARMY-HESS-PSEVDAS-TS

Issued by: Lighthief Farmy Fotowoltaiczne Sp. z o.o. (PL)

Date: 28 July 2026

Validity: 30 days

Status: Initial budgetary offer **FOR ISSUE**

1. Scope — 132/33 kV substation (KYEA) & TS connection

- **132 kV AIS connection bay:** HV apparatus, disconnectors, earth switches, surge arresters, CT/VT and ISM cable termination (per TSOC-approved design)
- **33 kV switchgear** (8 panels, eco-gas): 6 BESS feeders + transformer incomer + bus coupler; protection, control, RTU, telecom link to ECCC/TSOC, power-quality recorder
- **33 kV cable system** between the 6 MV skids and the KYEA (supply, laying, terminations, testing)
- **63 MVA 132/33 kV YNd11 ONAN/ONAF main transformer (T1) + 33 kV/400–230 V zig-zag earthing/auxiliary transformer (T2)**
- **Substation civil works:** foundations, oil containment, control building, cable trenches/ducts, internal roads, hardstanding, fencing; **station earthing** (T14 study + TSOC acceptance); **site fire-water system** (20 m³ tank, electric + diesel pump sets, hydrant network, hose reels)
- Protection design & settings (TSOC-approved), HV safety coordination, testing, energisation and as-built documentation

132/33 kV Substation & TS connection — turnkey EPC (ex-VAT)

€ 10,610,000

Of which: substation EPC/BoP € 8,900,000 · main & earthing/auxiliary transformers T1+T2 € 1,710,000 (assumed budget — firmed on binding manufacturer quotation to PT Technical Information v2.0, 170 kV BIL / 70 kV AC).

2. Terms

Currency	EUR, ex-VAT (Cyprus 19%, reclaimable), ex duties/fees
Validity	30 days
Delivery	Main transformer targeted on site Q1 2027; energisation subject to TSOC hold points
Payment	Standard EPC milestones; 5% performance bond; delay LDs per EPC framework
Contracting entity	Lighthief Farmy Fotowoltaiczne Sp. z o.o. (PL)

Excludes: VAT, duties and fees; the 132 kV cable from the existing Psevdas TS to the KYEA and any Psevdas TS extension (ISM scope); installation/programming of main & check meters (ISM/ISD — metering CT/VT included); ongoing telecom link fees. This is an initial budgetary offer; 33 kV switchgear, 132 kV bay, transformers and civil works are assumed budgets pending binding

supplier quotations, the TSOC-approved SLD (CT count) and the local civil BOQ. Compliance, exclusions and assumptions per the shared Offer Annexes (A & B).

Lighthief Farny Fotowoltaiczne Sp. z o.o. (Lighthief Group) · office@lighthief.com · **solarfarms.cy**

Confidential — for H.E.S.S. Hybrid Energy Storage Systems Ltd. Offer 3 of 3 (132/33 kV Substation & TS). 28 July 2026. Read with the Offer Annexes and Indicative Schedule.