

Teaser SLOMCZYN 13.9 MWp

READY-TO-BUILD PHOTOVOLTAIC FARM 13.9 MW • POLAND

13.9 MWp	€7.645M	12.4%	€550k/MWp
PV Farm Capacity	Total CAPEX	IRR (Base)	CAPEX/MWp

EXECUTIVE SUMMARY

The Slomczyn PV project with a capacity of 13.9 MW is fully prepared for implementation – the site has a complete set of documentation: lease agreements, grid connection conditions, building permit for the PV farm, building permit for the cable route. A replacement building permit decision needs to be made to update the components.

PROJECT LOCATION

Project	Capacity	Distance to Grid	Yield
Slomczyn	13.9 MWp	~5.5 km (MV)	1,080 kWh/kWp/year

KEY INVESTMENT HIGHLIGHTS

- RTB Status – all permits and project documentation secured
- RISEN 690 Wp modules – bifacial, N-type technology, high durability
- Sungrow SG350HX inverters, 12 MPPT, 99% efficiency
- 2 × 6.3 MVA – transformer stations compliant with PGE
- MV cable route ~5.5 km – complete documentation and approvals
- 25-year lease, with possibility of continuation/amendment
- Expected yield: 1,080 kWh/kWp
- Energization: January 31, 2027
- Competitive price: €550k/MW

RETURN ON INVESTMENT

Base scenario (€76/MWh): IRR 12.4%

TECHNICAL SPECIFICATION

Installed DC capacity	13.89 MWp
Grid AC capacity	13.89 MW
PV modules	RISEN 690 Wp
Mounting system	South-facing fixed structure
Specific yield	1,080 kWh/kWp
Annual production Y1	15,000 MWh
Module degradation	0.40% p.a.
System losses	1.40%

PROJECT DETAILS

Location	Slomczyn, Masovian Voivodeship, Poland
Total land area	16 ha
Land status	29-year lease
Grid connection	MV (~5.5 km)
Grid connection agreement	Secured
Building permit	Obtained
Construction completion	November 30, 2026
First energization	January 31, 2027
Operating period	29 years
Revenue structure	SPOT