

A/A	Description of Work / Equipment	Amount
Section A		
1	PV PANELS: Premium Plus Module 645 W TRINA BIFACIAL GLASS MONOCRYSTALLINE MODULE Shipping Cost + Insurance	€ 476,091
2	INVERTERS: Inverters -330 kW Huawei Product Warrantee: 10 Years Inverters Consumables - Communication Modules (fiber optics)& Parts Shipping Cost + Insurance	€ 224,875
3	Aluminium Solar Mounting System Set Product Warrantee: 25 Years Shipping Cost + Insurance	€ 320,435
4	Installation of Piles (piling)	
5	Electrical Parts & Consumables Cables DC Distribution 6mm 1/C (multiply by 2) Cables AC Distribution 800 V 4/C 95mm Cu Cables AC Distribution 22k V 95mm Al 1/C (multiply by 3) Power Quality Analyzer (material and installation) 22 KV SWITCHGEAR (PV, EAC, METERING) material and installation BESS 1MW/4MWh, includes 22 kV switchgear (material and installation) SKID (Transformer & LV Switchgear) (material and installation)	€ 1,529,125
6	Electrical Installation (calculate the length of the cables) Electrical Installation - Wiring - DC Electrical Installation - Wiring - AC Fiber Optics in plastic pipes material and installation per meter Lightning Protection material and installation	€ 75,660
7	FireFighting System (material)	€ 3,125
8	Installation PV System: Installation Mounting System & Photovoltaic Panels	€ 55,812
9	Civil Works Buildings excavations and trenches	€ 87,500
10	Civil Works - Fencing	€ 40,000
11	Civil Works - Man Holes - Digging	€ 1,250
12	CCTV System & Alarm & Security Monitoring	€ 25,000
13	Commissioning with EAC - Connection to Main D/B & Operation Supervision	€ 5,400
		€ 2,844,273
15	Performance Guarantees during Construction	
16	Professional Liability/Indemnity	€ 134,999
17	CAR & Public Liability Insurance	
18	Due to Article 11B for Tax Treatment in the Specific Type of Work 0% VAT	
	Total Cost	€ 2,979,272
	Cost per MW	€ 993,091